

# Wykaz zjazdów

przy przebudowie ul. Sikorskiego w Tomaszowie Lub

Lp	Km zjazdu ( lokalizacja) - strona	Szer. zjazdu  m	Długość utwardz zjazdu  m	Projektowana naw. zjazdu ogółem			Roboty ziemne		Krawęż nik beton. R-3 15x30  m	Opornik beton 12x25  m
				asfalta gr, 4 cm m2	kostka bruk. 8 nowa m2	kostka bruk. 8 z odzysku m2	W  m3	N  m3		
1.	0+080 P	5,00	3,00	-	-	40,0	-	-	-	-
2.	0+284 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
3.	0+312 P	3,50	2,00	10,60	-	-	-	5,0	7,50	-
4.	0+345 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
5.	0+352 P	3,50	2,00	10,60	-	-	-	5,0	7,50	-
6.	0+385 P	3,50	2,00	10,60	-	-	-	5,0	7,50	-
7.	0+392 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
8.	0+427 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
9.	0+448 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
10.	0+454 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
11.	0+475 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
12.	0+481L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
13.	0+509 L	3,50	1,80	-	9,80	-	1,0	-	-	4,0
14.	0+649 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0

15.	0+748 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0
16.	0+791 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0
17.	0+800 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0
18.	0+838 P	3,50	2,00	-	-	10,60	-	-	-	-
19.	0+844 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0
20.	0+849 L	3,50	1,80	-	-	9,80	0,5	-	-	4,0
21.	0+873 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
22.	0+879 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
23.	0+894 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
24.	0+918 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
25.	0+926 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
26.	0+934 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
27.	0+958 P	3,50	2,00	bez zmian	-	-	-	-	-	-
28.	0+965 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
29.	0+984 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
30.	1+034 L	3,50	2,56	-	-	12,80	1,0	-	-	9,0
31.	1+039 L	3,50	2,56	-	-	12,80	1,0	-	-	9,0
32.	1+054 L	3,50	2,56	-	-	12,80	1,0	-	-	9,0
33.	1+080 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
34.	1+093 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
35.	1+105 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0

36.	1+119 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
37.	1+140 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
38.	1+144 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
39.	1+158 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
40.	1+172 L	3,50	2,56	-	12,80	-	1,0	-	-	9,0
41.	1+173 P	3,50	2,00	10,60	-	-	2,0	-	7,50	-
<b>OGÓLEM 1 - 40 :</b>				<b>116,60</b>	<b>203,40</b>	<b>147,80</b>	<b>40,00</b>	<b>15,00</b>	<b>82,50</b>	<b>168,00</b>